

# Optional Parts for Geberit Duofix Carrier 111.434.00.1 and 111.490.00.1

## **Product Specifications**

Installation accessories for concealed carrier for wall-hung lavatories. Accessories shall be for alternate frame installation and connection sets between carrier and lavatory fixture.

## Warranty

One-year warranty against manufacturers' defect.

#### Features

Installation accessories for:

- Pre-wall installation
- Corner installation
- Post-tension concrete floors
- Non-standard stud distances
- Alternate bolts caps
- Finished wall thicknesses to 7.09" (18 cm)

### Mounting Accessories for Carrier Frames

Description		Model No.
Clan Clan	Frame to wall anchoring for 5.125"-7.875" (13-20 cm) thick unfinished pre-wall	111.815.00.1
Carlos and a second	Frame to wall anchoring for 5.125"-7.875" (13-20 cm) thick unfinished pre-wall corner installations	111.835.00.1
	Frame to wall anchoring where foot installations into floor are not allowed for 5.125"-7.875" (13-20 cm) thick unfinished pre-wall	111.867.00.1
	Fastening set for sinks with 14.9"-22.8" (38-58 cm) mounting centers	111.868.00.1
	Frame to stud fastening set for extended stud spacing from 19.75"-25.56" (50-65 cm)	111.869.00.1
	Frame to wall anchoring extensions for 7.87"-15.75" (20-40 cm) thick unfinished pre-wall	111.887.00.1
Co Co Co	Elbow supply fitting set, Gun Metal	465.034.00.1

## Lavatory Connection Accessories

0000

Cover caps with leveling washer, Plastic, Alpine White

## Required Accessories for 3.50"-7.00" (9-18 cm) Finished Wall Thickness



Mounting rod extension set for wall-hung lavatory, M10

217.713.11.1

242.233.00.1

Job Name		
Date	Quantity	
Model Specified		
Variations Specified		
Customer/Wholesaler		
Contractor		
Architect		

GNA7054 06/12